



TEST REPORT

No. **23997-23**

Page 1 of

ULR: TC71942300001494

SAMPLE DATA

Sample **RO Outlet**

Sender **Kothari International School**
- Pune

Container **1 no(s) 1 L Plastic Bottle, 1000 ml sample**

Sampling type **Grab**
Collected on **25-Apr-23 at 11:12 hrs**
Received at lab on **25-Apr-23 at 12:15 hrs**
Testing completed o **29-Apr-23**
Test results issued o **29-Apr-23**

Std. Ref. **IS 10500, Drinking Water - Specification (Abridged by Polytest Laboratories)**

TEST DATA

Test	Unit	Result	Reference Value	Test Method
1 Colour	Hazen	<1	< 5	APHA 23rd Edition, 2120 B
2 Total Dissolved Solids	mg/l	18	<500	IS 3025 (Part 16)
3 Turbidity	NTU	<0.5	<1	IS 3025 (Part 10)
4 pH	-	7.55	6.5 - 8.5	IS 3025 (Part 11)
5 Total Alkalinity (as CaCO3)	mg/l	6.6	<200	IS 3025 (Part 23)
6 Chloride (as Cl)	mg/l	3.97	<250	IS 3025 (Part 32)
7 Total Hardness (as CaCO3)	mg/l	4	<200	IS 3025 (Part 21)
8 Sulphate (as SO4)	mg/l	<1	<200	APHA 23rd Edition, 4500-SO4 E
9 Nitrate (as NO3)	mg/l	<1	<45	APHA 23rd Edition, 4500 NO3 B
10 Iron (as Fe)	mg/l	<0.075	<1	IS 3025 (Part 53)
11 Free Residual Chlorine	mg/l	0	min. 0.5**	IS 3025 (Part 26)

END OF NABL TEST DATA. OPINIONS, INTERPRETATIONS & REMARKS are at the end of this Test Report.



For Kothari International School
Signature
Manager



When reliability matters the mos



TEST REPORT

No. **23997-23**

Page 2 of

ULR: TC/1942300001494

TEST DATA

Test	Unit	Result	Reference Value	Test Method
12 Total Coliforms	CFU/100ml	not detected	Not Detectable	IS 5401 (Part 1)
13 E.coli	CFU/100ml	not detected	Not Detectable	IS 5887 (Part 1)

END OF TOTAL TEST DATA

OPINIONS, INTERPRETATIONS & REMARKS

- On the basis of above analysis, water is suitable for drinking.
- The results expressed as '<' are below Method Detection Limit.
- **Applicable only when water is chlorinated, for protection against bacterial and viral infection.
- The above parameters have been selected for all the practical purpose and end usage of water, more parameters may be tested as per the need of the application specific to the parameter's significance of suspected presence.
- The above mentioned standard values have been taken from IS 10500 - ACCEPTABLE VALUES. For details please refer the above Standard.
- The above analysis results pertain only to 'as received' sample and without prejudice to its source or proces
- The contents of this Test Report shall not be reproduced in part or in full in such a way that it will distort the
- The sampling is not done by Polytest Laboratories.
- The uncertainty value of test results is available upon request for the tests covered under our current scope of NABL accreditation.
- # The Test Method is not covered under our current scope of NABL accreditation.

END OF OPINIONS, INTERPRETATIONS & REMARKS

END OF TEST REPORT



Authorized by

Signature Not Verified
Digitally signed by SMT. AJAY KAPADNE
Date: 2023.04.29 14:21:55 +05:30
Location: pune

For Kothari International School
[Signature]
Manager

When reliability matters the mos

पाणी पुरवठा कार्यालय (मीटर)

पाणीपुरवठा(बंडगार्डन)

पुणे महानगरपालिका

उप अभियंता यांचे कार्यालय

जा.क्र. 461

दिनांक 01/04/2020

मा.उप अभियंता

बांधकाम नियंत्रण विभाग,

पुणे महानगरपालिका

झोन. ४

भाग स्कराडी (पार्ट N.O.C.)

विषय:- न हरकत दाखला

संदर्भ:- श्री. मयूर राहा व श्री. मिळींद कोळते फारिल यांचा
जा.क्र. ५९ दि. ११/६/२०२० चा नॉटिस N.O.C. अर्ज

- 1) घर क्रमांक/स.नं./फा. प्लॉट नं अ.न. ५५/५८/५५/२/१, स्कराडी
- 2) बांधकाम परवाना क्रमांक/ दिनांक ८८/३२५५/१५ दि. ३०/१२/२०१५
- 3) बांधकाम क्षेत्र १५२५.०५ चौ. मीटर (तिसऱ्या मजले सार्व
- 4) ग्राहक क्रमांक मिळकतील १ व्या मजले विंगर बरगुती नवजोड

सदर ठिकाणी झालेल्या बांधकाम/ वाढीव बांधकामास मीटर प्रमाणे पाणी पट्टी


दिनांक ते दिनांक स्वकम रु. चलन क्र.

दिनांक..... रोजी भरलेले आहेत.

तरी सदर ठिकाणी झालेल्या बांधकामास/ वाढीव बांधकामास पूर्णत्वाचा दाखला/ पार्ट पूर्णत्वाचा दाखला देण्यास मीटर विभागाची काही हरकत नाही.

मा.स. कळावे,

दिनांक


आमक अभियंता
बंड, पा. ५, (मीटर विभाग)


उप अभियंता

पाणी पुरवठा (मीटर विभाग)

उप अभियंता (मीटर)


बंडगार्डन पाणी पुरवठा विभाग

पुणे महानगरपालिका


०१/०४/२०२०



For Kothari International School


Manager

MR - BHAGWAN LAXMAN BHADALE

At - Post Uruli Devachi, Tal - Haveli, Dist - Pune - 412308

लायसेन्स प्लंबरचे नाव :- बी एल भाडळे
पत्ता :- मु.पो. ऊरुळीदेवाची, ता. हवेली
लायसेन्स क्र. 526 जि. पुणे
दिनांक :- 09/09/2020

मा उप अभियंता

वांछकाम नियंत्रण विभाग

पुणे महानगरपालिका

घांजकडे.....

विषय :- ड्रेनेज कामाबाबत.....

महोदय,

पुणे पेट ~~कोनेक्शन~~ पुणे घरांक स.न. 54/2/1 दि. 54/5B सब

प्लॉट नं. 13/5/2016 सोसायटीचे नाव येथील मालक सयूर शाहू शिंदे

याच्यावरील प्लॉट मधील इमारतीचे ड्रेनेज कनेक्शन चार्जस रु. 10,000/- चलन क्र. 16500 दि

13/5/2016 रोजी भरलेले आहेत. तसेच रस्ता खोदाई चार्जस रु. दि. भरलेले

आहेत व कार्यालयाकडील पत्र जा. क्र. 626 दि. 24/5/16 ने मान्य नकाशाप्रमाणे

माझ्या देखरेखीखाली समाधानकारकरित्या काम पुर्ण झालेले आहे. डाऊन टेक पाईप संडास बांधकामचे फिटिंग

संबंधी नियमाप्रमाणे वापरलेले आहे. पाईप व चेंबरला योग्य प्रमाणात उतार दिलेला आहे. चेंबर कव्हर आर.सी.सी

वापरले आहेत

कामामध्ये कोणत्याही प्रकारचा दोष राहिलेला नाही. (तिसरा मजला)

मा.स. कळाचे

आपला निश्वास

B. L. Bhadale
PMC LICENCE
Plumbing Contractor

For Kothari International School

Manager

